BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of Work: Improvements to drains kuvempu layout kempapura in ward no.07 byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	222.75	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications..	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	29.88	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification .	Cum	5905.51	Rupees Five Thousand Nine Hundred Five and Fifty One Paise Only
3	47.03	Providing and laying in plain reinforced cement concrete mix 1:2:4 with OPC @ 240 kgs, with 40 mm and down size graded granite matel coarse aggregates @ 0.84 cum and fine aggragtes @ 0.56cum, in pen foundations including including cost of all materials, labour HOM machinery form works scaffolding and centering complete as per sprcifications complete as per drawing anf techinal specifications.	Cum	5936.75	Rupees Five Thousand Nine Hundred Thirty Six and Seventy Five Paise Only
4	2.35	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	90596.08	Rupees Ninety Thousand Five Hundred Ninety Six and Eight Paise Only
5	796.80	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.	Sqm	483.36	Rupees Four Hundred Eighty Three and Thirty Six Paise Only
6	99.60	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
7	222.75	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification.	Cum	94.34	Rupees Ninety Four and Thirty Four Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
16/02

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))